

May 22, 2023

ADDENDUM No. 2

To become part of the Contract for the project:

**BID# 23-122 TOWN OF WATERFORD
PUBLIC SAFETY FACILITY AND POLICE STATION BOILER ROOM UPGRADES
WATERFORD, CT**

QUESTIONS AND ANSWERS:

- Q: Where is the intended location of the temporary water heater? What are the electrical specs?
A: The temporary electric water heater shall be located in the boiler room. A standard 40 gallon, 4500 watt, 208/1 volt water heater is to be provided. Contractor to provide 30A, 2P circuit breaker and wiring from boiler room panel.

DRAWING M1.1 PUBLIC SAFETY FACILITY MECHANICAL PARTIAL PLANS:

1. Refer to attached sketch MSK-1 for boiler condensate pipe route.

DRAWING M2.1 POLICE STATION MECHANICAL PARTIAL PLANS:

1. Detail 1/M2.1: Remove existing disconnect switches associated with the existing pumps.
2. Detail 2/M2.1: Install new fused disconnect switches furnished by pump manufacturer.
3. Detail 3/M2.1 Pump Schedule: ADD "Note #4: Provide optional fused disconnect switch for each pump."

Attachments:

Sketch MSK-1

+++++ END OF ADDENDUM No. 2 +++++

